

RENOVATIONS AT ENTOKOZWENI HALL EMAKHAZENI LOCAL MUNICIPALITY
(Labour and Material Contract)

Main Provisional Bills of Quantities

Item	Description	Unit	Qty	Rate	Amount
	<u>Bill No. 2</u> <u>Removal of Broken materials</u> <u>Gutters</u> Contractor is requested to remove all broken gutters including brackets, down pipes and holder bats and prepare the surface to put new PVC gutters including downpipes, joints etc. Remove:				
1	Gutters around the building	m	110		
2	Downpipes around the buildings	No	24		
3	Remove broken window pane in the conference hall, clean to receive new.	m ²	22		
	Total Amount c/f				R

RENOVATIONS AT ENTOKOZWENI HALL EMAKHAZENI LOCAL MUNICIPALITY
(Labour and Material Contract)

Main Provisional Bills of Quantities

Item	Description	Unit	Qty	Rate	Amount
	Total Amount b/f				R
	Remove broken window pane in the conference hall, clean to receive new.				
4	Replace window pane with new including patty and paint to match the existing.	m ²	12		
	Remove all broken WC complete set including 15mm flexi pipe and valves				
5	Male toilets	No	5		
6	Female toilets	No	8		
7	Stage ladies dressing room	No	1		
8	WHB including hot and cold water tap mixer with P or S-trap and stopper in the ladies stage dressing room	No	1		
9	Downpipes around the buildings	No	48		
10	Replace broken window pane in the conference hall, clean to receive new.	m ³	3		
11	Replace window pane with new including patty and paint to match the existing.	m ²	3		
	Replace all broken WC complete set including 15mm flexi pipe and valves				
12	Male toilets	No	5		
13	Female toilets	No	8		
14	Stage ladies dressing room	No	1		
	Total Amount Carried to Final Summary				R

RENOVATIONS AT ENTOKOZWENI HALL EMAKHAZENI LOCAL MUNICIPALITY
(Labour and Material Contract)

Main Provisional Bills of Quantities

Item	Description	Unit	Qty	Rate	Amount
	BILL No 3 New PVC Gutter Contractor is requested to carefully line - up straight line with slope not exceeding minimum requirement to outlet or offset				
1	Marley square gutter around the building	m	110		
2	Square stopend gutter	No	8		
3	Gutter external angle at the cornres	No	8		
4	PVC gutter joiners	No	48		
5	PVC gutter brackets	No	178		
6	PVC gutter down pipes	No	51		
7	PVC bends including shoes and all accessories.	No	76		
8	PVC Outlet	No	38		
	NB: Contractor is requested to put gutter holderbats or brackets in every 1,2m c/c to avoid gutter overweight of rainwater. All brackets must be fastened tight to avoid loose when rainwater is full.				
	Total Amount Carried to Final Summary				R

RENOVATIONS AT ENTOKOZWENI HALL EMAKHAZENI LOCAL MUNICIPALITY
(Labour and Material Contract)

Main Provisional Bills of Quantities

Item	Description	Unit	Qty	Rate	Amount
	BILL No 4 : CEILING WORK Office 1 Contractor is requested to carefully remove broken ceiling boards including bendrings and ceiling lights to prepare installation of new.				
1	Remove ceiling, bendrings and ceiling lights	m ²	20		
2	Replace ceiling boards with NuTech ceiling boards including clout nails and bishop strips	m ²	26		
3	Reinstate one ceiling light in the office including all wirings closure and terminating unwanted light connections.	No	2		
4	Nu-tech cornice sealed close to ceilin boards	m	22		
	ENTRANCE AND HALL Carefully remove all broken ceiling boards and all strips and align to receive new.				
5	Entrance hall	m ²	24		
6	Main hall where affected and shown during briefing session.	m ²	16		
7	Extra over ceiling boards laid elsewhere	m ²	12		
	Total Amount Carried to Final Summary				R

RENOVATIONS AT ENTOKOZWENI HALL EMAKHAZENI LOCAL MUNICIPALITY
(Labour and Material Contract)

Main Provisional Bills of Quantities

Item	Description	Unit	Qty	Rate	Amount
	BILL No 5 : DOOR LOCKS AND PAINT WORK				
	DOOR LOCKS				
	Contractor is requested to check all doors, align them and put new locks to all doors in the building.				
1	Ladies toilets	No	10		
2	Gents toilets	No	6		
3	Kitchen, conference hall and toilets	No	5		
4	Dressing room in ladies and gents (Stage)	No	4		
5	Entrance hall and main hall	No	8		
6	Offices	No	2		
7	Store	No	1		
8	Disability toilets	No	2		
	PAINT WORK				
	Contractor is requested to sandpaper the wall to receive new finishing paint.				
	Two coats of washable paint to match existing				
9	Hall and all toilets	m ²	478		
10	Office 1 and 2 in front	m ²	84		
11	Conference room and store room	m ²	99		
	Total Amount Carried to Final Summary				R

RENOVATIONS AT ENTOKOZWENI HALL EMAKHAZENI LOCAL MUNICIPALITY
(Labour and Material Contract)

FINAL SUMMARY

Item	Description	Page	Total Amount
1	Bill No. 1: Preliminaries	1	R
2	Bill No. 2: Removal of broken Materials	3	R
3	Bill No. 3: New PVC Gutters	4	R
4	Bill No. 4: Ceiling Work	5	R
5	Bill No. 5: Door Locks and Paint	6	R
	Sub-Total		R
	15% VAT		R
	Total Amount Tendered		R