

## Main Provisional Bills of Quantities

*Proposed Paving work at Mamahlola ECD Centre*

## Main Provisional Bills of Quantities

*Proposed Paving work at Mamahlola ECD Centre*

## Main Provisional Bills of Quantities

*Proposed Paving work at Mamahlola ECD Centre*

**EXTERNAL WORK - MAMAHLOLA ECD CENTRE  
(Labour and Material Contract)**

**Main Provisional Bills of Quantities**

| Item | Description                                                                                                                                                                                                                                                                                                          | Unit           | Qty | Rate | Amount |
|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|-----|------|--------|
|      | <p><b><u>BILL No 4</u></b></p> <p><b>PAVING WORK</b></p> <p>Contractor is requested to prepare and level ground to slope prepare, insecticides areas marked on the drawing before laying paving bricks, sloping of the ground paving must be placed around the building with 1m at the back away from the apron.</p> |                |     |      |        |
| 1    | Supply and lay 60mm Grey locking paving including 20mm sand bedding.                                                                                                                                                                                                                                                 | m <sup>2</sup> | 165 |      |        |
| 2    | Remove broken apron and put new with DPM underneath to prevent water damage on the sides and back of the building with 10MPa concrete                                                                                                                                                                                | m <sup>2</sup> | 59  |      |        |
| 3    | Other special test requested by SAFCOL (Compaction Test)                                                                                                                                                                                                                                                             | m <sup>2</sup> | 4   |      |        |
| 4    | 15MPa concrete on the edge of paving including 20mm sand bedding outside gate as on plan                                                                                                                                                                                                                             | m <sup>3</sup> | 2   |      |        |
| 5    | Close with well mixed mortar 110mm bend behind the building                                                                                                                                                                                                                                                          | Item           | 1   |      |        |
|      | Total Amount Carried to Final Summary                                                                                                                                                                                                                                                                                |                |     |      | R      |

## Main Provisional Bills of Quantities

*Proposed Paving work at Mamahlola ECD Centre*

**EXTERNAL WORK - MAMAHLOLA ECD CENTRE**  
**(Labour and Material Contract)**

**Main Provisional Bills of Quantities**

| Item | Description                                                                                                                                                    | Unit           | Qty | Rate | Amount      |
|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|-----|------|-------------|
|      | <b>BILL No 6</b><br><br><b>GATE ADJUSTMENT</b><br><br><b>Contractor is requested to compact, build on edge by<br/>enclose bricks to stabilize paving work.</b> |                |     |      |             |
| 1    | Plate compact with 3 passes                                                                                                                                    | m <sup>3</sup> | 2   |      |             |
| 2    | Brick and mortar on the edge of the pave                                                                                                                       | m <sup>2</sup> | 12  |      |             |
| 3    | Clean up all paving after work                                                                                                                                 | m <sup>2</sup> | 134 |      |             |
|      | <b>Contractor is requested to remove gate rail and replace<br/>with 12mm round bar welded to 3mm thick angle iron<br/>fixed with concrete</b>                  |                |     |      |             |
| 4    | 3mm thick angle iron (6m)                                                                                                                                      | No             | 2   |      |             |
| 5    | 12mm round bar welded (6m)                                                                                                                                     | No             | 2   |      |             |
| 6    | Clean up gate wheels and put back gate and align to fit<br>the opening                                                                                         | No             | 1   |      |             |
|      | <b>Electrical / Gas stove</b><br>Provisional                                                                                                                   | No             | 1   |      |             |
|      | Provide an amount of R12 000,00 (Twelve thousand<br>rands) for Electrical or Gas stove including plumbing<br>,19kg cylinder, pipping and all accessories.      |                |     |      |             |
| 7    | Install 4 x plate stove with oven mounted, include<br>isolator and wiring and testing or plumbing to gas stove                                                 | Item           | 1   |      | R 12 000,00 |
|      | Total Amount Carried to Final Summary                                                                                                                          |                |     |      | R           |

**EXTERNAL WORK - MAMAHLOLA ECD CENTRE**  
**(Labour and Material Contract)**

## FINAL SUMMARY

| Item | Description                              | Page | Total Amount |
|------|------------------------------------------|------|--------------|
| 1    | Bill No. 1: Preliminaries                | 1    | R            |
| 2    | Bill No. 2: Earth works (Site clearance) | 2    | R            |
| 3    | Bill No.3: Soil Poisoning                | 3    | R            |
| 4    | Bill No. 4: Paving Work                  | 4    | R            |
| 5    | Bill No. 5: Gap Filler                   | 5    | R            |
| 6    | Bill No. 6: Gate Adjustment              | 6    | R            |
|      | Sub-Total                                |      | R            |
|      | 15% VAT                                  |      | R            |
|      | Total Amount Tendered                    |      | R            |