

**EXTERNAL WORK - PAVING AT SIMILE CLINIC
(Labour and Material Contract)**

Main Provisional Bills of Quantities

Item	Description	Unit	Qty	Rate	Amount
	<u>Bill No. 2</u> <u>Removal of Existing Work</u> <u>Demolishing (Outside small entrance gate</u>				
1	Break down and remove small retaining broken wall, clean the area to receive new	m ²	19		
2	Remove broken ground tar, level to receive new pavement floors outside small gate.				
3	Break down and remove cracked old concrete paving, level and prepare to receive new walkways paving.	m ³	3		
	Removal of existing concrete work, rocks etc. Contractor is requested to remove all cracked floor concrete from walkways to prepare all new concrete work and levels				
4	Remove cracked concrete and level the ground to slope	m ³	2		
	Total Amount carried to final summary				R

**EXTERNAL WORK - PAVING AT SIMILE CLINIC
(Labour and Material Contract)**

Main Provisional Bills of Quantities

Item	Description	Unit	Qty	Rate	Amount
	BILL No 3 PAVING WORK Grey interlocking paving Contractor is requested to prepare and level ground to slope prepare, insecticides to all areas to be paved as shown during site briefing				
1	Supply and lay 50mm Grey cement paving including 20mm sand bedding, Outside small gate with edging at the end.	m ²	111		
2	Supply and lay 50mm Grey cement paving including 20mm sand bedding, inside small gate walkway 1,2m with to clinic with edging at the end.	m ²	72		
3	Permanently remove all unwanted weeds from floor	m ²	12		
4	Providing testing certificate and Pest control	Item	1		
	Plastic Under the paving 250mm micron green or equal approved sisalation laid on or under paving to avoid growth				
5	On walkways (From the gate to the edge of the clinic entrance)	m ²	40		
	Total Amount C/F				R

**EXTERNAL WORK - PAVING AT SIMILE CLINIC
(Labour and Material Contract)**

Main Provisional Bills of Quantities

Item	Description	Unit	Qty	Rate	Amount
	Total Amount C/F				R
	Retaining Wall Contractor is requested to build small wall to slope from the high side of the walkways Brick wall (NFP)				
6	230mm brick wall not exceeding 400mm high Wall outside small entrance gate	m ²	13		
7	Walls inside small gate walkways to the edge of the clinic.	m ²	17		
	CONCRETE WORK				
8	10MPa Conrete work laid on top of 250mm	m ³	2		
9	1,2mm widthto slope steps	m ³	1		
10	Reove wood hand rail on newly concreted steps slope and replace with 2,5mm x 75mm diameter steel round bar tube welded with 4 same size support at step interval encasted to newly laid conctere work.	Item	1		
	Total Amount Carried to Final Summary				R

**EXTERNAL WORK - PAVING AT SIMILE CLINIC
(Labour and Material Contract)**

FINAL SUMMARY

Item	Description	Page	Total Amount
1	Bill No. 1: Preliminaries	1	R
2	Bill No. 2: Removal of existing works.	2	R
3	Bill No. 3: Paving Work	4	R
	Sub-Total		R
	15% VAT		R
	Total Amount Tendered		R